

Sr.No.	Particulars	Unit	Qty.
1	1.1 KV, LT XLPE Cable	Rmt	15
2	RSJ Pole 4" x 4-1/2"	Nos	1
3	HT Conductor	Rmt	150
4	DP Structure for Transformer Mounting with 22 KV DO Set, AB Switch, LA Etc.	Set	1
5	63 KVA Distribution Box	Nos	1
6	22/0.44 KV 63 KVA Dist. Transformer	Nos	1
7	HT Stay Sets	Set	1
8	LT Cable Termination	Nos	2
9	LT Earthing Complete	Set	9
10	Miscellaneous Nut Bolt, Washer, Lugs Etc.	LS	1