

Quotation for compound wall at Open Plot.

Sr. No	Description Work	Unit	Qty.	Rate
1	Excavation of Soft and Hard Soil	Cum	135	
2	Providing and casting, leveling compacting PCC M-10 Concrete for bed leveling course, 100 mm thick, including curring etc.	Sqm	12.32	
3	Construction of UCR masonry in CM 1:6 for foundation and plinth, including racking joints and curring etc.	Cum	117	
4	Providing and casting copping on UCR masonry 100 mm thick in M-20 concrete, including scaffolding, curring etc.	Cum	5	
5	Providing and casting M-20 Concrete for foundation block for angle fixing size 450 x450x 450 mm	Cum	4.3	
6	Providing bending binding tor steel for copping	Kg	600	
7	Providing and fabriction of MS angle of 65x65x6 mm for chainlink fencing, fixing concrete block at 2.40 m c/c, Y shape, approximate lenth 3 mtr.	Kg	900	
8	Plastering with 1:6 ratio for copping and patta	Sqm	650	
9	Supplying and fixing GI chainlink fencing 50x50 mm 2.5 mm wire 1.2m high. Fixing in 8 mm bar	Sqm	135	
10	Supply and fixing of barbed wire 3 + 3 layer for Y	Rmt	672	
11	Supply and instalation of Razor fencing on top of fencing	Rmt	112	
12	Applying Silver paint for angle including primer coat	Rmt	110	

Total Amount Rs

